

## IPA 2011

### Construction of the capacities for minors and other vulnerable groups of illegal migrants in the Reception Centre for Aliens - Ježevo

#### QUESTIONS AND ANSWERS

**1. Publication reference**

EuropeAid/134761/M/WKS/HR

**2. Procedure**

Open

**3. Programme**

IPA

**4. Financing**

National Programme for Croatia under the IPA – Transition Assistance and Institution Building Component for 2011

**5. Contracting Authority**

Central Finance and Contracting Agency, Ulica grada Vukovara 284, objekt C, 10000 Zagreb, Croatia

QUESTIONS	ANSWERS
<p><b>Q1.</b></p> <p>In the Ježevo-New building-BoQ-12042013; D – Internal road and car park; D.I. – Road; III. Pavement structure;</p> <p>Item 13. Installation of grass paving grids. Elements are joined together in a way that adjacent element is lifted and joint are fixed. Calculation per m2 of paved surface.</p> <p>There is nothing sad in the d4u_techspec-en about shape, dimension or materials of the grass paving grids. Please send us more detailed description and specifications.</p>	<p><b>A1.</b></p> <p>Please note that grass paving grids were also referred to the Tender documentation, Volume 3 Technical specification, page 7, Point 1. Introduction, A.3.c Construction parcel with following description <i>“Parking areas and the fire and rescue service access are to be asphalted or polypropylene grass pavers shall be installed in compliance with the bearing capacity required for access as well as operational work of the fire rescue vehicles (100 kN/axial load)”</i>.</p> <p>Therefore following requirements are to be followed :</p> <ul style="list-style-type: none"><li>a) grass paving grids material is polypropylen</li><li>b) grass paving grids bearing capacity should be at least 100 kN/ axial load</li></ul>